

March 19, 2015

Addendum No. 1

To

PROJECT MANUAL  
and  
CONTRACT DOCUMENTS  
for  
OLD COURTHOUSE – NORTH ANNEX ROOFING  
2200 BROADWAY  
REDWOOD CITY, CALIFORNIA  
Project No. PF631

\*\*\*\*\*

Department of Public Works  
San Mateo County  
555 County Center, 5<sup>TH</sup> Floor  
Redwood City, California 94063-1665

By this Addendum, under the Scope of Work and Technical Specifications, Section 3.3 Coverboard Installation, ADD the following paragraph:

- F. Parapet Wall Flashings: Fasten 1/4 inch densdeck to all parapet wall surfaces where tear-off is to occur. Fill gaps exceeding 1/4 inch (6mm) with insulation. Cut and fit insulation within 1/4 inch (6mm) of nailers, projections, and penetrations. Extend coating to top of all parapet wall surfaces and 4 inches onto horizontal surfaces per manufacturer's instructions.